(*f*) That the timber prepared out of each tree shall be measured and stamped by the Range Officer or such other officer as the District Forest Officer may authorize, at the stump. Until the timber is marked at the stump, the timber shall not be removed.

(*g*) That he shall pay for all the timber measured as per clause (*f*) before removal from the forest or the depot fixed by the District Forest Officer.

(*h*) That all removals should be effected under passports issued by the Forest Officer in charge of the forest or depot and on presentation of the treasury receipt for the value of the timber he intends to remove.

(*i*) That if any tree other than the one bearing the departmental stamp impression or a tree that he has not purchased is felled, he will pay a fine not exceeding Rs. 15 per each tree.

(*j*) That the timber paid for, but not removed within six months of the termination of the contract shall lapse to Government.

(*k*) That he agrees to such timber as may not be paid for before the 15th June 1925 shall lapse to Government.

(*l*) That he agrees to abide by the rules of the department, as regards kindling of fires and holds himself responsible for any forest offences committed by his agents, employees and workmen.

(*m*) That he agrees to the cancellation of the contract and the forfeiture of his deposit for breach of any of the terms of the contract.

(*n*) That he agrees to maintain a register in the form prescribed by the District Forest Officer showing the serial number and kind of trees felled and the outturn of timber for each tree, which will be open to the examination of all Forest Officers.

*Note.*—Elephants could be hired when available on payment of a hire of Rs. 6 per male and Rs. 5 per female for a working day of six hours (rations for the elephants to be supplied by the hirer).

P. KRISHNASWAMI RAO,
*District Forest Officer.*

## ENGINEERING DEPARTMENT.

### KOLAR DIVISION.

*Notification dated 14th January 1925.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to 7th February 1925, for constructing a dispensary building and a maternity ward at Devarayasamudram. An approximate estimate of quantities is given below. The sequantities are not guaranteed. These work should be completed by the end of September 1925.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the forms given below, showing the rates at which the differeent items specified will be executed.—

| Description of work | Unit of work | Rate per unit |
|---|---|---|
| | | |

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty (Rs. 150) in cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing a dispensary building and maternity ward at Devarayasamudram," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the approximate estimate quantities of work to be done for construcng a dispensary building and maternity ward at Devarayasamudram.

| Serial No. | Items of work | Per | Dispensary | Maternity ward | Kitchen for Maternity ward | Kitchen for Dispensary | Latrine |
|---|---|---|---|---|---|---|---|
| 1 | Earthwork excavation and filling in basement .. | C. yd. | 50 | 47 | 4 | | 4 |
| 2 | Concrete in mortar .. .. .. | C. ft. | 394 | 421 | .. | | .. |
| 3 | Burnt stone in chunam .. .. .. | ,, | 1,311 | 1,097 | 173 | | 110 |
| 4 | Burnt brick in chunam .. .. | ,, | 1,722 | 1,600 | 195 | | 166 |
| 5 | Plastering with chunam .. . .. | Sqr. | 30·59 | 29·56 | 5·29 | | 4·15 |
| 6 | White and colour washing .. .. | ,, | 30·59 | 29·66 | 5·29 | | .. |
| 7 | Teak wood work wrought and put up .. | C. ft | 83·81 | 46·00 | 11·42 | | .. |
| 8 | Rooling with 1st class Mangalore tiles on teak reepers, etc., complete. | Sqr. | 12·91 | 10·66 | 1·92 | | .. |
| 9 | Ridge tiles set in mortar with cement pointing.. | R. ft. | 31 | 31 | 15 | | .. |
| 10 | Flooring with Cudapah slabs on 3" concrete bed and cement pointing. | Sqr. | 1·65 | 2·83 | ·70 | | .. |
| 11 | Flooring with Mangalore square tiles over 3" concrete bed and cement point ng. | ,, | 4·80 | 2·40 | .. | | .. |
| 12 | Burnt stone slabs 6" thick dressed .. .. | S. ft. | 167 | 269 | 15 | | .. |
| 13 | Teakwood battoned do rs with double shutters with iron clamps, etc., complete. | ,, | 112 | 142 | 18 | | .. |
| 14 | Teakwood windows with panelled and glazed shutters with ¾" iron bars clamps, etc., complete. | ,, | 113 | .. | 5 | | .. |
| 15 | Teakwood ventilators with glazed shutters, etc., complete. | ,, | 9 | 12 | .. | | .. |
| 16 | Silicate paining or chacolate .. .. | Sqr. | 5·80 | 4·03 | ·46 | | .. |
| 17 | Teakwood pillars with base and capitals dressing | Each | 4 | .. | .. | | .. |
| 18 | Chunnam borders .. .. .. | R. ft. | 80 | .. | 37 | | .. |
| 19 | Providing almirah in compounding room 3½' x 4½' with teak planks 1" thick. | Each | 2 | .. | .. | | .. |
| 20 | Providing wooden racks in the stone room .. | Lumpsum | | .. | .. | | .. |
| 21 | Chunam pointing .. .. .. | Sqr | 2·47 | 2·24 | .. | | Lumpsum |
| 22 | Clearing site and leveling ground .. .. | Lumpsum | | .. | .. | | .. |
| 23 | Wood oiling .. .. .. | Do | | .. | .. | | Lumpsum |
| 24 | Tarring .. .. .. .. | Do | | .. | .. | | .. |
| 25 | Ventilating tiles .. .. .. | Each | .. | .. | 4 | | Lumpsum |
| 26 | Conducting V shaped drain .. .. | Lumpsum | | | | | " 38¼ |
| 27 | Providing drainage arrangements alround the building. | .. | .. | .. | .. | | |
| 28 | Coping over wall with plastering .. .. | R. ft. | .. | .. | .. | | .. |
| 29 | Teakwood battened shutters with frames for shelves. | S. ft. | .. | 56 | .. | | .. |
| 30 | Teakwood plank 1" thick for shelves .. | ,, | .. | 34 | .. | | .. |
| 31 | Providing teakwood racks, and cistern wall in bath room. | Lumpsum | | .. | .. | | .. |
| 32 | Teakwood pillars with base and caps complete 5" x 5" square | No. | .. | 5 | .. | | .. |
| 33 | Teakwood buttened windows with iron bars, including glazed shutters, etc., complete. | S. ft. | .. | 36 | .. | | .. |

As per column 6.

As per column 6.

R. L. STEELE,
*Executive Engineer,*

## SPECIAL WATER-SUPPLY CONSTRUCTION DIVISION.

*Abstract Notification, dated 19th December* 1924.

The attention of the public is hereby invited to the detailed notice calling for sealed tenders for the construction of the Filter beds, Service Reservoir, Settling tanks, Watchmen shed and Temporary office shed for water-supply to Tumkur Town" published in pages 5 to 8 of Part VI of the *Mysore Gazette*, dated 1st January 1925. The last date for receiving the tenders is 12 noon of 3rd February 1925.

H. F. MARKER,
*Executive Engineer.*
*Special Water-Supply Construction Division*